1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104 An ALION Technical Center

Test Report

RIVERBANK.ALIONSCIENCE.COM FOUNDED 1918 BY WALLACE CLEMENT SABINE

SPONSOR: Riverbank Acoustical Laboratories

Geneva, IL

Sound Transmission Loss RALTM-TL21-080

CONDUCTED: 2021-02-26

Page 1 of 8

ON: 8 inch thick solid core concrete (no ceiling)

TEST METHODOLOGY

Riverbank Acoustical Laboratories™ is accredited by the U.S. Department of Commerce, National Institute of Standards and Technology (NIST) under the National Voluntary Laboratory Accreditation Program (NVLAP) as an ISO 17025:2017 Laboratory (NVLAP Lab Code: 100227-0) and for this test procedure. The test reported in this document conformed explicitly with ASTM E90-09 (2016): "Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements." The single number rating of the specimen was calculated according to ASTM E413-16: "Classification for Rating Sound Insulation." A description of the measurement procedure and room specifications is available upon request. The transmission loss values are for a single direction of measurement. The results presented in this report apply to the sample as received from the test sponsor.

INFORMATION PROVIDED BY SPONSOR

The test specimen was designated by the sponsor as 8 inch thick solid core concrete (no ceiling). The following nominal product information was provided by the sponsor prior to testing. The accuracy of such sponsor-provided information can affect the validity of the test results.

Product Under Test

Material: Solid core concrete; local aggregate, grey cement

Manufacturer: Dukane Precast

SPECIMEN MEASUREMENTS & TEST CONDITIONS

The construction contractor (Seth Priser) and RAL staff compiled a detailed construction specification as follows, in order of installation:

Concrete Slab

Material: Precast concrete

Dimensions: 4 @ 610 mm (24 in.) x 4267 mm (168 in.)

Thickness: 203 mm (8 in.)

Overall Weight: 5023.08 kg (11074 lbs)
Mass per Unit Area: 482.75 kg/m² (98.875 lbs/ft²)

Installation: Laid in test opening over 152.4 mm (6 in.) wide knee walls constructed

from isolated wood framing

Joint undersides sealed with acoustical caulk and tape

Top of joints filled with general purpose sand, sealed with premixed

masonry joint compound



® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2017 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.

1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104

An ALION Technical Center

RIVERBANK.ALIONSCIENCE.COM
FOUNDED 1918 BY
WALLACE CLEMENT SABINE

Test Report

Riverbank Acoustical Laboratories 2021-02-26

RALTM-TL21-080 Page 2 of 8

Overall Specimen Measurements

Dimensions: 2.44 m (96.0 in) wide by 4.27 m (168 in.) long

Thickness: 0.2 m (8.0 in)

Weight: 5023.08 kg (11074.0 lbs)

Overall Area: 10.405 m² (112 ft²)

Mass per Unit Area: 482.75 kg/m² (98.88 lbs/ft²)

Test Aperture

Opening Size: $4.27 \text{ m} (14.0 \text{ ft}) \times 6.10 \text{ m} (20.0 \text{ ft})$

Filler Wall: Yes

Aperture Size: 2.44 m (96.0 in) wide by 3.86 m (152.0 in) long

Transmission Area: 9.414 m² (101.33 ft²)

Sealed: Entire periphery (both sides) with dense mastic

Test Environment

Source Room

Volume: 130.71 m³

Temperature: $22.9 \,^{\circ}\text{C} \pm 0.0 \,^{\circ}\text{C}$ Relative Humidity: $40.65 \,^{\circ}\text{M} \pm 0.1 \,^{\circ}\text{M}$

Receive Room

Volume: 82.6 m³

Temperature: $23.4 \,^{\circ}\text{C} \pm 0.1 \,^{\circ}\text{C}$ Relative Humidity: $39.85 \,^{\circ}\!\!\!/ \pm 0.9 \,^{\circ}\!\!\!/$

Requirements

Temperature: 22° C +/- 2° C, not more than 3° C change over all tests.

Relative Humidity: $\geq 30\%$, not more than $\pm -3\%$ change over all tests.



1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104 An \triangle L I O N Technical Center

Test Report

RIVERBANK.ALIONSCIENCE.COM FOUNDED 1918 BY WALLACE CLEMENT SABINE

RALTM-TL21-080

Page 3 of 8

Riverbank Acoustical Laboratories 2021-02-26



Figure 1 – Specimen mounted in test opening, as viewed from source room



Figure 2 – Specimen mounted in test opening, as viewed from receive room



® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2017 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.

1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104 An ALION Technical Center

RIVERBANK.ALIONSCIENCE.COM FOUNDED 1918 BY WALLACE CLEMENT SABINE

Test Report

RALTM-TL21-080

Page 4 of 8

Riverbank Acoustical Laboratories 2021-02-26

TEST RESULTS

Sound transmission loss values are tabulated at the eighteen standard frequency bands. A graphic presentation of the data and additional information appear on the following pages. The precision of the transmission loss test data is within the limits set by the ASTM Standard E90-09 (2016). See Appendix A for identification of corrections applied to the reported data.

FREQ.	<u>TL</u>	ΔTL	DEF.	FREQ.	<u>TL</u>	ΔTL	DEF.
100	38	0.57	0	800	61	0.38	0
125	44	0.89	0	1000	64	0.34	0
160	42	0.82	3	1250	66	0.36	0
200	44	0.35	4	1600	69	0.37	0
250	44	0.50	7	2000	69	0.42	0
315	52	0.22	2	2500	73	0.38	0
400	52	0.23	5	3150	75	0.36	0
500	55	0.26	3	4000	76	0.35	0
630	57	0.25	2	5000	78	0.41	0

STC=58

ABBREVIATION INDEX

FREQ. = 1/3 OCTAVE BAND CENTER FREQUENCY, Hz

TL = TRANSMISSION LOSS, dB

 $\Delta TL = 95\%$ CONFIDENCE INTERVAL FOR TL MEASUREMENTS, dB

DEF. = DEFICIENCIES, dB BELOW SHIFTED STC CONTOUR (SUM OF DEF = 26)

STC = SOUND TRANSMISSION CLASS

Tested by

Marc Sciaky

Senior Experimentalist

Report by

Malcolm Kelly

Test Engineer, Acoustician

Approved by

Eric P. Wolfram *Laboratory Manager*

TESTING

NVLAP LAB CODE 100227-0

® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2017 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.

1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104 An ALION Technical Center

Test Report


RIVERBANK.ALIONSCIENCE.COM
FOUNDED 1918 BY
WALLACE CLEMENT SABINE

RALTM-TL21-080 Page 5 of 8

Riverbank Acoustical Laboratories 2021-02-26

SOUND TRANSMISSION REPORT

8 inch thick solid core concrete (no ceiling)



STC=58

TRANSMISSION LOSS
SOUND TRANSMISSION CLASS CONTOUR



® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2017 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.

1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104

An ALION Technical Center

Test Report

RIVERBANK.ALIONSCIENCE.COM
FOUNDED 1918 BY
WALLACE CLEMENT SABINE

Riverbank Acoustical Laboratories 2021-02-26

Page 6 of 8

APPENDIX A: Extended Frequency Range Data

Specimen: 8 inch thick solid core concrete (no ceiling) (See Full Report)

The following non-accredited data were obtained in accordance with ASTM E90-09 (2016), but extend beyond the defined frequency range of 100Hz to 5,000Hz. These unofficial results are representative of the RAL test environment only and intended for research & comparison purposes. Sampling precision observed during this procedure is reported below. Corrections are detailed in Appendix B.

1/3 Octave Band	Sound			
Center Frequency	Transmission Loss	Applicable	ΔTL (Eq. A2.5)	Repeatability
(Hz)	(dB)	Corrections	(dB)	(dB)
31.5	36	ZZ F	1.41	16.75
40	36	ZZ F	1.38	5.77
50	35	ZZ F	1.54	3.98
63	34	ZZ F	0.62	0.75
80	36	ZZ F	0.79	1.46
100	38	ZZ F	0.57	3.83
125	44	ZZ F	0.89	0.97
160	42	Z F	0.82	1.35
200	44	ZZ F	0.35	1.21
250	44	Z F	0.50	0.56
315	52	Z F	0.22	0.61
400	52	Z F	0.23	0.76
500	55	Z F	0.26	0.58
630	57	Z F	0.25	1.03
800	61	Z F	0.38	0.34
1000	64	Z F	0.34	0.78
1250	66	Z F	0.36	1.09
1600	69	Z	0.37	1.47
2000	69	Z	0.42	1.14
2500	73	Z	0.38	0.87
3150	75		0.36	0.90
4000	76		0.35	1.95
5000	78	ZA	0.41	3.09
6300	75	ZA	0.48	5.31
8000	71	Z	0.46	7.87
10000	64	ZA	0.47	6.75
12500	57	Z	0.44	6.94



® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2017 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.

1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104 An ALION Technical Center

Test Report

RIVERBANK.ALIONSCIENCE.COM FOUNDED 1918 BY WALLACE CLEMENT SABINE

RALTM-TL21-080
Page 7 of 8

Riverbank Acoustical Laboratories 2021-02-26

APPENDIX B: Glossary of Standardized Corrections and Adjustments

Specimen: 8 inch thick solid core concrete (no ceiling) (See Full Report)

Mark Interpretation

- A Measured sound pressure levels in the receive room are within 10 dB of the ambient noise level at the marked frequency band. Receive room levels used to calculate Transmission Loss are corrected according to ASTM E90 Section 10.3.
- Measured sound pressure levels in the receive room are within 5 dB of the ambient noise level at the marked frequency band. Receive room levels used to calculate Transmission Loss are corrected according to ASTM E90 Section 10.3.1. Transmission Loss values calculated from levels corrected this way will be less than or equal to Transmission Loss values from a hypothetical test using the same specimen and a receive room with idealized ambient sound levels of (-\infty) dB.
- F The reported Transmission Loss is within 10 dB of the laboratory flanking limit at the marked frequency band. The measured performance of the specimen may be limited by the performance of the laboratory building structure at this frequency band.
- Z The reported Transmission Loss at the marked frequency band has been corrected according to ASTM E90 Section A3.2.7 to account for possible sound transmission through the filler assembly.
- The reported Transmission Loss at the marked frequency band has been corrected according to ASTM E90 Section A3.2.8 to account for possible sound transmission through the filler assembly. Transmission Loss values corrected this way will be less than or equal to Transmission Loss values from a hypothetical test using the same specimen and an idealized filler assembly with a Sound Transmission Class rating of (∞) .

APPENDIX C: Glossary of Variability Metrics

Specimen: 8 inch thick solid core concrete (no ceiling) (See Full Report)

ΔTL, the 95% confidence interval for reported transmission loss values, is calculated from the standard deviation of the sets of measurements for source room sound pressure level, receive room sound pressure level, and receive room sound absorption. This metric is calculated in an effort to quantify the combined influences of room geometry, microphone positioning, and other varying environmental conditions on reported results.

Repeatability, expressed as a 95% confidence interval, is calculated from the standard deviation of transmission loss as obtained from a set of six (6) consecutive tests conducted according to this test method by RAL from 2021-02-25 through 2021-03-04. The tests were performed on a specimen composed of a nominal 6 inch thick concrete slab, using the same test opening as used in this report. This metric provides an estimate of the variation in results that might be observed if the test were repeated with no change to the installed specimen. Note that repeatability will vary with the construction type.



® RIVERBANK ACOUSTICAL LABORATORIES IS ACCREDITED BY NVLAP (LAB CODE 100227-0) FOR ACOUSTICAL TESTING SERVICES IN ACCORDANCE WITH ISO/IEC 17025:2017 AND FOR THIS PROCEDURE. THIS REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY RAL, NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.

1512 S BATAVIA AVENUE GENEVA, IL 60134 630-232-0104 An ALION Technical Center

RIVERBANK.ALIONSCIENCE.COM FOUNDED 1918 BY WALLACE CLEMENT SABINE

Page 8 of 8

Test Report

RALTM-TL21-080

Riverbank Acoustical Laboratories 2021-02-26

APPENDIX D: Instruments of Traceability

Specimen: 8 inch thick solid core concrete (no ceiling) (See Full Report)

Description	Model	Serial Number	Date of Certification	Calibration <u>Due</u>
System 2	Type 3160-A-042	3160- 106974	2020-08-13	2021-08-13
Bruel & Kjaer Mic And Preamp C	Type 4943-B-001	2311439	2020-04-07	2021-04-07
Bruel & Kjaer Pistonphone	Type 4228	2781248	2020-08-12	2021-08-12
EXTECH Hygro 662 EXTECH Hygro 663	SD700 SD700	A083662 A083663	2020-12-18 2020-12-18	2021-12-18 2021-12-18

APPENDIX E: Revisions to Original Test Report

Specimen: 8 inch thick solid core concrete (no ceiling) (See Full Report)

Date	Revision
2021-05-19	Original report issued



